



Mechanism 10A intermediate MW

WBM10I-MW

Architecture	
Type of control unit	rocker
Configuration	
- intermediate	
Main electrical features	
Nominal voltage	250 V
Electric current	
Rated current	10 A
Installation, mounting	
Screws properties	terminal screws backed off
Installation mode	RotoLoc ®
Connection	
Type of connection	Screw connection
- terminals accommodate 4 x 1.5 mm² cable	
- with screw terminals	
Identification	
Main design line	Mechanisms